

1.0 GENERAL REQUIREMENTS:

1.1 SCOPE OF WORK:

Work includes, but is not limited to base bid, providing all labor and transportation for striping, and services required to stripe pavement requested by Georgia Ports Authority (GPA) at the Garden City Terminal.

- Contractor shall install thermoplastic numbers and double yellow lines in each of the RMG bomb cart slots in the Mason yard.
- Contractor shall provide any/all material and equipment necessary for the installation of 5" wide White Thermoplastic traffic type paint needed for cross terminal road and berth road.
- Contractor shall provide any/all equipment, labor, and material necessary for the installation of 5" wide Yellow Thermoplastic traffic type paint needed for cross terminal road and berth road.

1.2 CODES AND STANDARDS:

The Contractor shall be responsible for complying with regulations of all local, state, and federal agencies having jurisdiction over any portion of the work to be performed under this contract.

The Contractor, as a minimum, shall meet or exceed the applicable requirements of the latest revision of the following codes and specifications published by the following organizations:

ANSI	AMERICAN NATIONAL STANDARDS INSTITUTE
ASTM	AMERICAN SOCIETY OF TESTING MATERIALS
DOT	DEPARTMENT OF TRANSPORTION
EPA	ENVIRONMENTAL PROTECTION AGENCY
NFPA	NATIONAL FIRE PREVENTION ASSOCIATION
OSHA	OCCUPATIONAL SAFETY AND HEALTH ACT
SSPC	STEEL STRUCTURES AND PAINTING COUNCIL

All work shall be in compliance with Section 653 (Thermoplastic Traffic Stripe) of the GDOT standard specification

It is not the intent of this specification to restrict the Contractor's work. The Contractor shall be totally responsible for the work. These specifications are the minimal requirements acceptable to GPA.

1.3 COORDINATION OF WORK/AND INSPECTION:

Contractor shall be responsible for coordinating all work to be performed under this project with the Maintenance Assistant manager. Contractor shall turn in daily time sheets reflecting work done for that day. Additionally, Contractor shall provide documentation of equipment on site and/or utilized daily.

1.4 GPA INSPECTIONS/WARRANTS:

All work performed shall be subject to inspection by Georgia Ports Authority. Contractor shall notify the Maintenance Assistant Manager prior to completion of work to allow for GPA inspection of Contractor's work. The Contractor at no cost to Georgia Ports Authority shall correct any deficiencies caused by the Contractor's work. All Contractors' work other than striping shall be warranted for one year from completion of the projects.

1.5 CONTRACTOR'S QUALIFICATIONS:

Contractor shall have a minimum of three (3) years experience.

**Thermoplastic Paint Installation
Garden City CB1,2,3 Stack Roads, ICTF, Tomochichi
Performance Specification**

1.6 CONTRACTORS WORK HOURS:

All normal work for this contract shall be performed during normal daylight hours. Any exceptions will require the written approval of the Maintenance Assistant Manager.

If work is required during nighttime the Contractor will be required to furnish safe, proper and sufficient lighting arrangements in order to receive such approval.

Work will be required on weekends to avoid interruptions in Georgia Ports Authority operations.

1.7 SITE ACCESS ON GPA FACILITIES:

Access to the site shall be across properties owned by Georgia Ports Authority.

Access through gates controlled by Georgia Ports Authority will be coordinated through the Maintenance Assistant Manager.

1.8 SAFETY:

The successful Contractor agrees to adhere to and enforce all applicable local, state, federal, and OSHA safety regulations.

Contractor shall install GPA provide safety barriers, as required, to clearly identify the working area and to prevent others from accessing the work area. This safety zone shall be sufficiently sized to prevent damage to others or existing facilities and structures.

Upon completion of the work, Contractor shall remove the safety barriers from the work area, and cleanup the work area of all materials, debris, dirt, ECT.

Any accidents, injuries, fires or other incidents of a serious nature or incidents requiring emergency response must be reported immediately to the GPA Police Department at (912) 964-3911.

1.9 ENVIRONMENT PROTECTION:

All used paint containers shall be properly disposed of in the mixed 30 yd recycled containers.

Protect river, canals, drainage ditches from chemical contamination, sediment runoff, construction debris, and other damage.

If material, equipment, or debris is sunk in river or canal, mark location to warn traffic, Maintenance Assistant Manager, and promptly recover sunken object.

Soil erosion, pollution and sediment control provisions and maintenance in accordance with local, state, and federal requirements will be required.

In case of a spill or release of any sort, Contractor shall immediately notify GPA's Environmental Response Coordinator at (912) 964-3842.

1.10 DEBRIS:

Do not permit debris or unsalvageable material resulting from the work to accumulate on site.

Remove debris as rapidly as it accumulates.

Do not dispose of debris in waterways.

**Thermoplastic Paint Installation
Garden City CB1,2,3 Stack Roads, ICTF, Tomochichi
Performance Specification**

Provide for off-site disposal areas.

1.11 DISPOSAL OF MATERIALS OFF GPA'S PROPERTY:

Contractor shall coordinate dispose of all materials with the Maintenance Assistant Manager.

Contractor shall furnish copies to GPA of all transportation and disposal receipts for all products, Materials disposed of by the contractor.

Contractor shall indemnify and hold harmless GPA from any expenses, damages, or claims asserted against or incurred by GPA as a result of Contractor's work or disposal of materials off GPA's property.

1.12 MAINTAINING TRAFFIC:

Accomplish Work with minimum interference to pedestrian, vehicular, crane, equipment, and rail traffic on-site and on adjacent streets and highways and marine traffic in waterways.

1.13 GPA FACILITIES:

Existing berths, crane, storage yards, roadways, warehouses, and surrounding areas will be in daily use by GPA operations and will remain so during the work. Contractor shall not interfere with GPA's use of the existing facilities.

Contractor shall not enter any of the GPA's warehouses or buildings, without authorization by the Maintenance Assistant Manager.

Unless otherwise approved by GPA, Contractor shall confine activities to the immediate work project site.

Contractor shall not unreasonably encumber the work area with materials or equipment.

Contractor shall keep the work area clean at all times and shall promptly remove waste materials or rubbish.

1.14 FINAL INSPECTION:

The Contractor shall notify the Maintenance Assistant Manager prior to completion to allow for adequate time for inspection of Contractor's work.

All work performed shall be subject to inspection by Georgia Ports Authority.

The Contractor at no cost to Georgia Ports Authority shall correct any deficiencies.

1.15 CONTRACTOR FURNISHED MATERIAL/EQUIPMENT

Contractor shall provide transport vehicle, all employee personal protective equipment (PPE), Hard hats, safety vest, gloves, steel toe shoes and cleaning products.

1.16 PRICING:

Thermoplastic RMG bomb cart slots (line/numbers)

Per foot price for thermoplastic lines, up to 20,000ft